

SUMMARY

The jetty for the South Hook LNG Import Terminal was constructed between 2005 and 2007. Works included refurbishment of the approach trestle for re-use within the terminal, demolition of some of the structures that were no longer required, and

new construction of the berthing line. This paper reviews the methods that were adopted and discusses how some of the challenges were overcome.